

PLUGGING RECORD

Instructions: Within thirty days following the plugging of a dry hole, or the abandonment of a producing well, the owner or operator shall submit this form in duplicate for wells on patented or Federal lands, and in triplicate for wells on State lands. Geological information will be held confidential for a period of twelve months if requested in writing. Fill out form as completely as possible.

Operator

STANCO Petroleum, Inc.

Address

P.O. Box 202, Kimball, NE 69145

Well Number

#13

Lease Name

Peterson Unit 17400

Field and reservoir (If wildcat, so state)

Vowers "D" Sand

Location

C SE NE

Sec. 33

Twp. 17N

Range 54W

County

Banner

Footage Location

1983 ft. from (N) (S) line, 671

ft. from (E) (W) line of NE

1/4

Spud Date

6-13-56

Date reached T.D.

6-23-56

Date Plugged

7-31-93

Total Depth

6003'

P. B. T. D.

5870'

Elevation

4715.9'

Reference (indicate)

(K) (GL) (WF)

Producing rate on initial completion

Oil (bbls/day)

125

Gas (MCF/day)

0

Water (bbls/day)

0

Application to drill this well was filed in name of:

Producing rate at time of abandonment

Oil (bbls/day)

1

Gas (MCF/day)

0

Water (bbls/day)

40

CONDITION OF HOLE

Name each formation containing oil or gas. Indicate which formations open to well bore at time of plugging.

Fluid Content

Depth Interval

Size, kind and depth of plugs used. Indicate zones squeeze cemented giving amount of cement.

"D" Sand

Oil & Water

5769-5774

Sand to above perforations

5 sacks cement on top of sand

15 sacks bottom of surface pipe

10 sacks top of surface pipe

Size, kind and depth of any additional plugs

CIBP set at 5870' with 1 sack of cement on top

CASING RECORD


Size casing in O. D.	Weight lbs/ft.	Setting Depth	Amount Recovered	Amount left in well	Method of parting (shot, rioped, etc.)
8 5/8"	29.35	487	-	487	N/A
4 1/2"	9.5	5979	800'	5179	Shot

Was hole filled with mud-laden fluid? Yes

If this well was plugged back for use as a fresh water well, give pertinent details of plugging operations to base of fresh water sand. Attach letter from surface owner authorizing completion of this well as a fresh water well and agreeing to assume full liability for subsequent plugging which may be required.

I/We hereby swear or affirm that the statements herein made are complete and correct.

(If new dry hole, complete well log on reverse side of form)



Dallen J. Juel
Signature

President

Title

8-12-93

Date